


Installation manual

R32 split series



RXP20M5V1B RXP25M5V1B RXP35M5V1B

ARXP20M5V1B ARXP25M5V1B ARXP35M5V1B

Installation manual R32 split series

English

CE - ATTIKTIES-DEKLARACUA CE - ATBILSTIBAS-DEKLARĀCUA CE - VYPLASENIE-ZHOOY CE - UYGUNLUK-BEYANI	öych la deklaracja dotyczy. zestał decirajne: arach staracka: Juliv vanastik; Arach raw njeungagum; Arach raw njeungagum; Riecza Sokaracja; Riecza Sokaracja; U donanminni asjagidak gbi oduğunu beyan eder:	negbelinek az alábbi szabvány lok)rak vagy egyeb iányadó dokumentum (ok)rak. ha azokat előrás szeinnt hasznáják: spelnáją wymogy naskeptyacych norm i mych odkumentum vomalezevynych, pod warunkem že używane są zgodnie z naszymi instlukcjami: sunt in conformitate cu urmátorul (urmádanele) standantele) sau alt(e) documentle) nomativél), cu condiția ca acestea să fe utilizate în conformitate cu sistant zastantanti indugimi nomativi, pod pogojem, da se uporabljalo v skadu z nasimi navodii: on vastavuses jāgmist (je standanti (e)ga vă teste nomativi sebe dokumentlega, kui ned kasutalace vastanta mee ju jendiele: afinina zemiau nuodyus sandartus († ata) (kus nomminus odkumentus us salyga, kai y ra laudojami paga misų nuodymus. tal ja lieloti atalvasta szchiga nuradymem athist sekojošem standarinen un cibem nomativiem chkumentem: v notes s rasiedomoulymi) normoulami) alebo inými() normativnymi() dokumentum (m), za prechokladu, že sa používajú v sláde s našim nakodom: urnim, talimatian muza göre kullanimas i koşuluyle aę ajdaki standartia ve norm belifen begelerie vyumudur:	Direktver, med senere ændringer. Direktver, med foretagana aduringer. Direktver, med foretagana aduringer. Direktver, med foretalte endringer. Direktiver, med foretalte endringer. Direktiver, der foretalte endringer. Direktiver, der senere experience. Direktiver, der senere experience. Direktiverse su paldinmas. Dire		Dalkin Europe N.V. je pooddaššen za sestavo dabteke s tehnično mapo. Dalkie Europe N.V. o novlatudukoskana tehnišno kolkommentasonom. Dalkie Europe N.V. vo novlatudukoskana krita sa reswievecka ochrpykupe. Dalkie Europe N.V. je a galoid sadranfiš lechnine škorstukcjios falig. Dalkie Europe N.V. in a galoid sadranfiš lechnine škorstukcjios falig. Spladonsch Dalkie Europe N.V. je opravnera vlyvoni slubc nekolek skorštukcje. Spladonsch Dalkie Europe N.V. je opravnera vlyvoni slubc nekolek skorštukcje. Dalkie Europe N.V. Teknik Yap Dosysan derlemeje yetkildir.
CE - IZAVA O SKLADNOSTI CE - VASTAVUSDEKLARATSIOON CE - JEKNAPALINSAR-CAOT BETCTBME	deklarije na wlasna i wyklazną odpowiedzalność, że urządzenia, których ta deklaragia ddycz; debetarje odpowiedzalność, że urządzenia, których ta deklaragia ddycz; debetarje propie każydnied ce deklaragia na na kaleno se zięna ranska. Z vso odpownościo zjałaja, da je opema napava na kałeno se zięna ranska. Z vso odpownościo zjałaja, da każonie a ekklaradskoni ala kuniuv vanstus: permapuja se osos orrospowor, ve ofospigaseło za so odposenia każ jarya, kunia alkoma się odkarają. Woski kasano zakompowor, ve ofospigaseło za powienia kiloria alkoma się odkarają. Wiakają se z powienia się odkarają: y włastyja se za każnia się odkarają. Wydasyja se każ każ zadebon na które su vzłanie toto wyklasene: tamamen kerdi sroumi używać omak üzere bu blidnim igii ddużu donamnim sąsydak gbi odużunu bejan eder:	nagbelinek az alábbi szabvány(ok)rak vagy egyéb inányadó dokumenhun(ok)rak, ha azokat előrtás szeninthasznáják spekiają wymogi nasépujących normi innych obdumentów normielzenytnych, pod warunkem že używare są spochoż z naszymi instukcjo sunt in conformiate zu urmátokul (urmátoarek) standardje) sau alle) documentje) normativje), ou condija ca acestea sá fie utirzate in co structychne kontroli or organia	Directhes, as amended. Directhes, parils Andeurg, parils Andeurg, parils Andeurg, 11 Directhes, leles que modifiees. 12 Directhes, seguin loemended. 13 Directhes, seguin loemendado. 14 Directhes, come de modifica. 15 Cotypus, omne, spour, pormorable; 16 Directhes, conforme alteração em. 17 Diperona ou sesua motipasacam. 17 Diperona ou sesua motipasacam. 17	inexxa* isorno engoneno s Qb. ii outereno ronoxivirenno or 48 contracio Ceprindonera 40- ii on nestina 40- ii adio noti unestina 40- ii adio noti	19** 20** 21** 22** 17** 23** 24** 24** 25**
CE - IZJAVA-OUSKLABENOSTI CE - MEGFEL EL ÓSÉGA-WILLATKOZAT CE - DEKLARACIA-ZGODNÓSGI CE - DECLARAȚIE-DE-CONFORMITATE	17 (8) 19 (8) 10 innebăr att. 19 (8) 19 (9) 19 (9) 10 (9) 10 (9) 11 (9) 12 (9) 12 (9) 13 (9) 14 (9) 15 (9) 16 (9) 17 (8) 18 (9)	16 17 17 18 18 18 18 18 18 18 18 18 18 18 18 18	5/EU * \$85 2/EC ** \$85 899	alzi (4b alapján, aži) (4b gazolla a meglédélési, aži, ži 3afenewsa* 4cb tamústkány szerit. 2c Pastaba* godníe zdobumentalag 4b, pozykwną popilą 4b) świadectwem (4c) asa oum este stabiti in 4b, si apreciat pozitiv de GB 2 prezimes* in condomise ou Gerffantalu (4c). kol je dolceno (4b) indobleno sistani (4B) v składu scerifikatom (4c). nagu on náčalud dokumentis (4b) ja hasis kidetud (25 Nor* 6B) jági vistanati serrifikaadile (4c).	Dakin Europe N.V. on valtuutettu baatimaan Teknisen asiakirjan. Geodochs Dakin (puppe N.V. na Optivarie le kompilado soutboru technické konstrukce. Dakin Europe N.V. je opesta za zazad Datoleke plenirčkoj konstrukcej. Dakin Europe N.V. je opesta a miszaki konstrukciós okournenlado foszaalilitására. A Dakin Europe N.V. ma upoviazhiene do zberanie i oprazonywania okolumenladi konstrukcijnej. Dakin Europe N.V. seste autorizat sa compleze Dosa ul temic de constitucije.
CE - ERKILÆRINO OM SAMSVAR CE - ILNOTTIS-YHDENMIKAISUUDESTA CE - PROHLÁŠENÍ-OSHODĚ	завляет, икслючительно под свою ответственность, что оборудование, к которому относится настоящее заявление enfacer under eneasyral gat utdystic, some or orithatet de deme enfactant detacer are indisatog, an invudensaria, gat utustingen som befor so denne dektaration innebår att. enfacer et lutskendig ansvar for at det utskir som betores av denne dektaration innebår er att. inntessa yekinomason vallag massar for at det utskir som betores av denne dektaration innebår er att. inntessa yekinomason vallag massar for at det utskir som betores av denne dektaration innebår er att. inntessa yekinomason for statt. Se zatterit, k remuz, se top potofisken vatalug inntessation vastionn odgovornskuld oprema na koju se ova tjava odnosi teles feletissege tudataban tiglent, togg a berendezesek, meljekte e nylatkocat voratkockit.	eguinte(s) rorma(s) rorma(s) rorma(s) rorma(s) rormar rorman rore	Low Voltage 2014/35/EU Electromagnetic Compatibility 2014/30/EU Machinery 2006/42/EC	Indir (A) cch godicarts av (B) entigt Certifikaet (C). Som def termonmer i CAo og genom positiv 17 Uwaga* som def termonmer i CAO og genom positiv 17 Uwaga* Idva on exitety assiarinassa (A) ja pida 18 Nota* Idva on exitety assiarinassa (A) ja pida 18 Nota* Idva on exitety assiarinassa (A) ja pida 19 Cpomba* (B) v souldou's osveledberim (C). Idva ja positivine zjišten (B) v souldou's osveledberim (C). Idva ja positivine zjišten (B) v souldou's osveledberim (C).	13** 14** 16** 17** 17**
CE - DECLARAÇÃO-DE-CONFORMIDADE CE - SARBITEME-Q-COOTBETCTBIAM CE - OVERENSSTRAMELSESERKLÆRING CE - FÓRSÁKRAN-OM-ÖVERENSTAMMELSE	09 assenser, worne 10 ex efferer under en 11 © ceferer regins 12 exterer et luisis 13 em imiteas et luisis 14 @ printistije ne sor 14 @ printistije ne sor 15 @ izjevlije pod ski 16 @ lejes febiSsej 16 @ lejes febiSsej	8 80 1	ob upsteranju dodož: vastalar hodelee: costalarinus narjame a: lakanis nuosalu, pelekiam; lakanis nuosalu, pelekiam; elekoju prasiko, sa nodeklas; bunun koşullama uygun darak;	the guidical positionmente da 11 Information* firate <c>. 12 Ment* to de A xox you'cro Bracé to de A you'cro Bracé to de C A you'cro Bracé to de C A you'cro Bracé to de C A you'cro C A you'cro techo em 4A e com o parece positivo 13 Huom* the come o C Bracéano CA. 4A you con C definication C A. 4A you contractivo C Bargerein C T Bracéanika* contractivo C Bargerein C T Bracéanika* > og possitivi vurderet af 4B i Ihenhold fil 15 Napomena*</c>	 07* Η Dalkin Europe NV, είνα εξουσοδοπμένη για συντίξα τον Τέγινά φάκολο κατισικευής. 06* Α Dalkin Europe NV, εκεί audorázel a compliera comentação Petro de fabro. 06* Kolmanen Dalkin Europe NV, esta dudorázel a compliera contractiva Roumen Tresuveración plonymentaции. 17* Dalkin Europe NV, esta dudoses et la sundanéje de tehnoke konstruktionséjan. 17* Dalkin Europe NV, de radioses et la sommarsiála den tehniske konstruktionsfilen. 17* Dalkin Europe NV, har fillateles II a kompliere den Tekniske konstruktionsfilen.
CE - DECLARACION-DE-CONFORMIDAD CE - DICHIARAZIONE-DI-CONFORMITA CE - AMAZIN ZYMMOPOAZENE	Daikin Europe N.V. 10 decises under its sale responsibility that the equipment to which this decistation relates: 12 of exitation and be decised for a days and statement and the entire of the entir	are in conformity with the following standard(s) or other normative document(s), provided that these are used in accordance with our instructions: derived by lighter by the following standard(s) or other normative document(s), provided that these are used in accordance with our instructions: sont continues & leavan normie(s) ou authe(s) document(s) normatif(s), pour authet qu'ils soient utilisés conformément à nos instructions: controllement annement et aux normies de leavan normie(s) ou authe(s) document(s) normative); prometif(s), pour authet qu'ils soient et az worden gébruik overent-formists instructions: sont conformi all is seguente(s) standard(s) o altro(s) document(s) normativo, siempre que sean utilizados de acuerdo con nuestas structiones: sont conformi all is seguente(s) standard(s) o altro(s) documento(s) normativo, und tryn ripoimééen den springionativo und acuer de la conformita alle nostre istruction; det acuerdo con nuestas structiones: conformative la conformita alle nostre istruction; det acuerdo provinción produziones (s) o altro(s) documento(s) scorovierus (normativo de suprimento) acuerdo provinción de la conformita alle nostre istruction; det acuerdo provinción provinción de la conformita alle nostre istruction; del documento del del provinción provinción de la conformita alle nostre istruction; del documento del del del del provinción del del del del del provinción del del del provinción del del del del del provinción del del del del del del del provinción del del del del del provinción del	10 under lagitagelse af bestemmelseme i: 19 ob upo 11 endgrukkomer. 20 vastem 12 git hemhod ti bestemmelseme i: 21 cnapa 13 moultetem määnkyää. 22 laikanta 14 ac dorbran ulashroveni pledissu. 23 leieting pemen dioridama. 15 pemen dioridama. 16 kövela (2); 24 odrbran 17 apodrie 2 postanowieniam Dyrektyw. 25 bunun 18 inuma prevedeflor:	r 06 Nota* v	Dalkin Europe N.V. is authorised to compile the Technical Construction File. Bakin Europe N.V. and deber-eitigung of de-fermische Konstudiorischet zusammenzustellen. Bakin Europe N.V. sist autrosé à compiler le Dossier de Construction Technique. Bakin Europe N.V. is bevoegd om hel Technisch Constructiedrossier samen te stellen. Dalkin Europe N.V. set autorizzad a redigere II File Technisch Construction Technique. Dalkin Europe N.V. set autorizzad a redigere II File Technica of Costruction.
CE - DECLARATION-OF-CONFORMITY CE - KONFORMITÄTSERKLÄRUNG CE - DECLARATION-DE-CONFORMITE CE - CONFORMITEITSVERKLARING	Daikin Europe N.V. If all declars under its sole responsibil con exist and serior alleright bearing C of exist and serior alleright bearing C of declare sous as seule responsibil control of a declar apply a unitar responsibil control of cont	of are in conformity with the following standards decident biggerden Normeien) oder einem a unseren Anweisungen eingesetzt werden: os sont conformes à Blaux normels) ou autie instructies: os estain en conformidant con la(s) signientels instructiones: os sono conform al(i) seguentel) standard(s) or sivon dupavant pt no(c) cokholoek(o) mothor de un prodriffes page.	10 following the provisions of: 02 general death viscoralities der 03 conformément aux sipulations des: 04 overent-foundrist get begalingen van: 05 sigulated las de Rossiciones de: 06 secondo le prescrizioni per: 07 par injourna va foundique van: 08 de accido com o previsio en: 09 a coor recrister non xelentament.	01 Note* as set out in <a>> and judged positively by according to the Certificate <c>> 02 Hinweis* with in <a>> detailed and <a>> detailed and <a>> detailed and <a>> detailed positiven to defined <a>> de acuerdo con el Certificado <a> de acuerdo con el Certificado <a>> de acuerdo con el Certificado <a> de acuerdo con el Certificado <a>> de acuerdo</c>	01** Daikin Europe N.V. is authorised to o 02** Daikin Europe N.V. hat de Berechtig 03** Daikin Europe N.V. est autorise 4 on 04** Daikin Europe N.V. is bevegid on he 05** Daikin Europe N.V. est autorizado a 06** Daikin Europe N.V. è autorizado a

Hiromitsu Wasaki
DAIKIN EUROPE N.V.
Director
Ostend, 21st of December 2018 care particulor particul

Table of contents

1			documentation
	1.1		this document
2		out the	
	2.1		or unit
		2.1.1	To unpack the outdoor unit
		2.1.2	To remove the accessories from the outdoor drift
3	Pre	parati	on
	3.1	Prepar	ing the installation site
		3.1.1	Installation site requirements of the outdoor unit
		3.1.2	Additional installation site requirements of the
	3.2	Proper	outdoor unit in cold climatesing refrigerant piping
	5.2	3.2.1	Refrigerant piping requirements
		3.2.2	Refrigerant piping length and height difference
		3.2.3	Refrigerant piping insulation
4		tallatio	
	4.1		ng the units
	4.0	4.1.1	To open the outdoor unit
	4.2	Mounti 4.2.1	ing the outdoor unit
		4.2.1	To install the outdoor unit
		4.2.2	To provide drainage
		4.2.4	To prevent the outdoor unit from falling over
	4.3		cting the refrigerant piping
		4.3.1	About connecting the refrigerant piping
		4.3.2	Precautions when connecting the refrigerant piping
		4.3.3	To connect the refrigerant piping to the outdoor unit
	4.4	Check	ing the refrigerant piping
		4.4.1	To check for leaks
		4.4.2	To perform vacuum drying
	4.5	_	ng refrigerant
		4.5.1	About charging refrigerant
		4.5.2	About the refrigerant
		4.5.3 4.5.4	To determine the additional refrigerant amount
		4.5.4	To determine the complete recharge amount To charge additional refrigerant
		4.5.6	To fix the fluorinated greenhouse gases label
	4.6		cting the electrical wiring
		4.6.1	Specifications of standard wiring components
		4.6.2	To connect the electrical wiring on the outdoor unit
	4.7	Finishi	ng the outdoor unit installation
		4.7.1	To finish the outdoor unit installation
		4.7.2	To close the outdoor unit
5	Cor	nmies	sioning
•	5.1		•
	5.1		list before commissioninglist during commissioning
	5.2		form a test run
	5.4		g up the outdoor unit
			2 -F 200000
3		posal	
	6.1		ew: Disposal
	6.2		np down
	6.3		rt and stop forced cooling
		6.3.1	To start/stop forced cooling using the indoor unit ON/ OFF switch
		6.3.2	To start/stop forced cooling using the indoor unit
			user interface
7	Tec	hnica	l data

1 About the documentation

About this document 1.1



INFORMATION

Make sure that the user has the printed documentation and ask him/her to keep it for future reference.

Target audience

Authorised installers

Documentation set

This document is part of a documentation set. The complete set consists of:

- General safety precautions:
- Safety instructions that you MUST read before installing
- Format: Paper (in the box of the outdoor unit)
- Outdoor unit installation manual:
 - Installation instructions
 - Format: Paper (in the box of the outdoor unit)
- Installer reference guide:
 - Preparation of the installation, reference data,...
 - Format: Digital files

Latest revisions of the supplied documentation may be available on the regional Daikin website or via your dealer.

The original documentation is written in English. All other languages are translations.


Technical engineering data

- A subset of the latest technical data is available on the regional Daikin website (publicly accessible).
- The full set of latest technical data is available on the Daikin extranet (authentication required).

2 **About the box**


2.1 **Outdoor unit**

2.1.1 To unpack the outdoor unit




7.1 Wiring diagram.

3 Preparation



To remove the accessories from the 2.1.2 outdoor unit

- 1 Lift the outdoor unit.
- 2 Remove the accessories at the bottom of the package.



- General safety precautions Outdoor unit installation manual
- Fluorinated greenhouse gases label
- Multilingual fluorinated greenhouse gases label Drain plug (located on the bottom of the packing case)

3 **Preparation**

3.1 Preparing the installation site





WARNING

The appliance shall be stored in a room without continuously operating ignition sources (example: open flames, an operating gas appliance or an operating electric

3.1.1 Installation site requirements of the outdoor unit

Mind the following spacing guidelines:






Air outlet

It is recommended to install a baffle plate when the air outlet is


It is recommended to install the outdoor unit with the air inlet facing the wall and NOT directly exposed to the wind.



- Baffle plate Prevailing wind direction
- Air outlet

3.1.2 Additional installation site requirements of the outdoor unit in cold climates

Protect the outdoor unit against direct snowfall and take care that the outdoor unit is NEVER snowed up.



- Snow cover or shed Pedestal
- Prevailing wind direction
- Air outlet

In any case, provide at least 300 mm of free space below the unit. Additionally, make sure the unit is positioned at least 100 mm above the maximum expected level of snow. See "4.2 Mounting the outdoor unit" on page 5 for more details.

In heavy snowfall areas it is very important to select an installation site where the snow will NOT affect the unit. If lateral snowfall is possible, make sure that the heat exchanger coil is NOT affected by the snow. If necessary, install a snow cover or shed and a pedestal.

See also

■ 4.2 Mounting the outdoor unit [▶ 5]

4

3.2 Preparing refrigerant piping

3.2.1 Refrigerant piping requirements

• Piping material: Phosphoric acid deoxidised seamless copper.

Piping diameter:

Liquid piping	Ø6.4 mm (1/4")
Gas piping	Ø9.5 mm (3/8")

Piping temper grade and thickness:

Outer diameter (Ø)	Temper grade	Thickness (t) ^(a)	
6.4 mm (1/4")	Annealed (O)	≥0.8 mm	Ø
9.5 mm (3/8")	Annealed (O)		\bigcirc t

(a) Depending on the applicable legislation and the unit's maximum working pressure (see "PS High" on the unit name plate), larger piping thickness might be required.

3.2.2 Refrigerant piping length and height difference

What?	Distance
Maximum allowable pipe length	15 m
Minimum allowable pipe length	1.5 m
Maximum allowable height difference	12 m

3.2.3 Refrigerant piping insulation

Pipe outer diameter (Ø _p)	Insulation inner diameter (Ø _i)	Insulation thickness (t)
6.4 mm (1/4")	8~10 mm	≥10 mm
9.5 mm (3/8")	12~15 mm	




If the temperature is higher than 30°C and the humidity is higher than RH 80%, the thickness of the insulation materials should be at least 20 mm to prevent condensation on the surface of the insulation.


4 Installation

4.1 Opening the units

4.1.1 To open the outdoor unit








4.2 Mounting the outdoor unit


4.2.1 To provide the installation structure

Prepare 4 sets of M8 or M10 anchor bolts, nuts and washers (field supply).



In any case, provide at least 300 mm of free space below the unit. Additionally, make sure the unit is positioned at least 100 mm above the maximum expected level of snow. In this case, it is recommended to construct a pedestal.

4.2.2 To install the outdoor unit



(A)RXP20~35M5V1B R32 split series 3P519299-5B – 2018.12 DAIKIN

Installation manual

4 Installation

4.2.3 To provide drainage



NOTICE

If the unit is installed in a cold climate, take adequate measures so that the evacuated condensate CANNOT freeze.



INFORMATION


For information on the available options, contact your dealer



NOTICE

Provide at least 300 mm of free space below the unit. Additionally, make sure the unit is positioned at least 100 mm above the expected level of snow.

- 1 Use a drain plug for drainage.
- 2 Use a Ø16 mm hose (field supply).




- Drain port Bottom frame

- Hose (field supply)

4.2.4 To prevent the outdoor unit from falling

In case the unit is installed in places where strong wind can tilt the unit, take following measure:

- 1 Prepare 2 cables as indicated in the following illustration (field
- 2 Place the 2 cables over the outdoor unit.
- Insert a rubber sheet between the cables and the outdoor unit to prevent the cables from scratching the paint (field supply).
- 4 Attach the ends of the cables and tighten them.



4.3 Connecting the refrigerant piping



6

DANGER: RISK OF BURNING

4.3.1 About connecting the refrigerant piping

Before connecting the refrigerant piping

Make sure the outdoor and indoor unit are mounted.

Typical workflow

Connecting the refrigerant piping involves:

- Connecting the refrigerant piping to the indoor unit
- · Connecting the refrigerant piping to the outdoor unit
- Insulating the refrigerant piping
- Keeping in mind the guidelines for:
- Pipe bending
- Flaring pipe ends
- Using the stop valves

Precautions when connecting the 4.3.2 refrigerant piping



DANGER: RISK OF BURNING



CAUTION

- Use the flare nut fixed to the main unit.
- To prevent gas leakage, apply refrigeration oil only to the inside of the flare. Use refrigeration oil for R32.
- Do NOT reuse joints.



WARNING

Connect the refrigerant piping securely before running the compressor. If the refrigerant piping is NOT connected and the stop valve is open when the compressor is run, air will be sucked in. This will cause abnormal pressure in the refrigeration cycle, which may result in equipment damage

4.3.3 To connect the refrigerant piping to the outdoor unit

- Piping length. Keep field piping as short as possible.
- Piping protection. Protect the field piping against physical
- 1 Connect the liquid refrigerant connection from the indoor unit to the liquid stop valve of the outdoor unit.



- Liquid stop valve
- Gas stop valve
- 2 Connect the gas refrigerant connection from the indoor unit to the gas stop valve of the outdoor unit.



NOTICE

It is recommended that the refrigerant piping between indoor and outdoor unit is installed in a ducting or the refrigerant piping is wrapped with finishing tape.

4.4 Checking the refrigerant piping

4.4.1 To check for leaks



NOTICE

Do NOT exceed the unit's maximum working pressure (see "PS High" on the unit name plate).



NOTICE

Make sure to use a recommended bubble test solution from your wholesaler. Do not use soap water, which may cause cracking of flare nuts (soap water may contain salt, which absorbs moisture that will freeze when the piping gets cold), and/or lead to corrosion of flared joints (soap water may contain ammonia which causes a corrosive effect between the brass flare nut and the copper flare).

- 1 Charge the system with nitrogen gas up to a gauge pressure of at least 200 kPa (2 bar). It is recommended to pressurize to 3000 kPa (30 bar) in order to detect small leaks.
- 2 Check for leaks by applying the bubble test solution to all connections.
- 3 Discharge all nitrogen gas.

4.4.2 To perform vacuum drying

- 1 Vacuum the system until the pressure on the manifold indicates -0.1 MPa (-1 bar).
- 2 Leave as is for 4-5 minutes and check the pressure:

If the pressure	Then
Does not change	There is no moisture in the system. This procedure is finished.
Increases	There is moisture in the system. Go to the next step.

- 3 Vacuum the system for at least 2 hours to a manifold pressure of −0.1 MPa (−1 bar).
- **4** After turning the pump OFF, check the pressure for at least 1 hour.
- **5** If you do NOT reach the target vacuum or CANNOT maintain the vacuum for 1 hour, do the following:
 - Check for leaks again.
 - Perform vacuum drying again.



NOTICE

Make sure to open the stop valves after installing the refrigerant piping and performing vacuum drying. Running the system with the stop valves closed may break the compressor.

4.5 Charging refrigerant

4.5.1 About charging refrigerant

The outdoor unit is factory charged with refrigerant, but in some cases the following might be necessary:

When
When the total liquid piping length is more than specified (see later).
Example:
 When relocating the system.
After a leak.

Charging additional refrigerant

Before charging additional refrigerant, make sure the outdoor unit's **external** refrigerant piping is checked (leak test, vacuum drying).



INFORMATION

Depending on the units and/or the installation conditions, it might be necessary to connect electrical wiring before you can charge refrigerant.

Typical workflow – Charging additional refrigerant typically consists of the following stages:

- 1 Determining if and how much you have to charge additionally.
- 2 If necessary, charging additional refrigerant.
- 3 Filling in the fluorinated greenhouse gases label, and fixing it to the inside of the outdoor unit.

Completely recharging refrigerant

Before completely recharging refrigerant, make sure the following is

- 1 All refrigerant is recovered from the system.
- 2 The outdoor unit's external refrigerant piping is checked (leak test, vacuum drying).
- 3 Vacuum drying on the outdoor unit's **internal** refrigerant piping is performed.



NOTICE

Before completely recharging, perform vacuum drying on the outdoor unit's **internal** refrigerant piping as well.

Typical workflow – Completely recharging refrigerant typically consists of the following stages:

- 1 Determining how much refrigerant to charge.
- 2 Charging refrigerant.
- 3 Filling in the fluorinated greenhouse gases label, and fixing it to the inside of the outdoor unit.

4.5.2 About the refrigerant

Refrigerant type: R32

Global warming potential (GWP) value: 675



NOTICE

In Europe, the **greenhouse gas emissions** of the total refrigerant charge in the system (expressed as tonnes ${\rm CO_2}$ equivalent) is used to determine the maintenance intervals. Follow the applicable legislation.

Formula to calculate the greenhouse gas emissions: GWP value of the refrigerant × Total refrigerant charge [in kg1 / 1000

Please contact your installer for more information.



WARNING: FLAMMABLE MATERIAL

The refrigerant inside this unit is mildly flammable.



WARNING

The appliance shall be stored in a room without continuously operating ignition sources (example: open flames, an operating gas appliance or an operating electric heater).

(A)RXP20~35M5V1B R32 split series 3P519299-5B – 2018.12 DAIKIN

Installation manual

4 Installation



WARNING

- Do NOT pierce or burn refrigerant cycle parts.
- Do NOT use cleaning materials or means to accelerate the defrosting process other than those recommended by the manufacturer.
- Be aware that the refrigerant inside the system is odourless.



WARNING

The refrigerant inside the unit is mildly flammable, but normally does NOT leak. If the refrigerant leaks in the room and comes in contact with fire from a burner, a heater, or a cooker, this may result in fire, or the formation

Turn off any combustible heating devices, ventilate the room, and contact the dealer where you purchased the

Do NOT use the unit until a service person confirms that the part from which the refrigerant leaked has been

4.5.3 To determine the additional refrigerant

If the total liquid piping length is	Then
≤10 m	Do NOT add additional refrigerant.
>10 m	R=(total length (m) of liquid piping–10 m)×0.020
	R=Additional charge (kg) (rounded in units of 0.01 kg)



INFORMATION

Piping length is the one-way length of liquid piping.

4.5.4 To determine the complete recharge amount



INFORMATION

If a complete recharge is necessary, the total refrigerant charge is: the factory refrigerant charge (see unit name plate) + the determined additional amount.

4.5.5 To charge additional refrigerant



8

WARNING


- Only use R32 as refrigerant. Other substances may cause explosions and accidents.
- R32 contains fluorinated greenhouse gases. Its global warming potential (GWP) value is 675. Do NOT vent these gases into the atmosphere.
- When charging refrigerant, ALWAYS use protective gloves and safety glasses.

Prerequisite: Before charging refrigerant, make sure the refrigerant piping is connected and checked (leak test and vacuum drying).

- Connect the refrigerant cylinder to the service port.
- 2 Charge the additional refrigerant amount.
- 3 Open the gas stop valve.

4.5.6 To fix the fluorinated greenhouse gases label

1 Fill in the label as follows:



- If a multilingual fluorinated greenhouse gases label is delivered with the unit (see accessories), peel off the applicable language and stick it on top of a
- Factory refrigerant charge: see unit name plate Additional refrigerant amount charged
- Total refrigerant charge
- Greenhouse gas emissions of the total refrigerant charge expressed as tonnes CO2 equivalent
- GWP = Global warming potential



NOTICE

In Europe, the greenhouse gas emissions of the total refrigerant charge in the system (expressed as tonnes CO₂ equivalent) is used to determine the maintenance intervals. Follow the applicable legislation.

Formula to calculate the greenhouse gas emissions: GWP value of the refrigerant × Total refrigerant charge [in kg] / 1000

2 Fix the label on the inside of the outdoor unit near the gas and liquid stop valves

4.6 Connecting the electrical wiring



DANGER: RISK OF ELECTROCUTION



WARNING

- All wiring MUST be performed by an authorised electrician and MUST comply with the applicable legislation.
- Make electrical connections to the fixed wiring.
- All components procured on-site and all electrical construction MUST comply with the applicable legislation.



WARNING

ALWAYS use multicore cable for power supply cables.



WARNING

If the supply cord is damaged, it MUST be replaced by the manufacturer, its service agent or similarly qualified persons in order to avoid a hazard.



WARNING

Do NOT connect the power supply to the indoor unit. This could result in electrical shock or fire.



WARNING

- Do NOT use locally purchased electrical parts inside
- Do NOT branch the power supply for the drain pump, etc. from the terminal block. This could result in electrical shock or fire.



DAIKIN

WARNING

Keep the interconnection wiring away from copper pipes without thermal insulation as such pipes will be very hot.

4.6.1 Specifications of standard wiring components

Component		
Power supply cable	Voltage	220~240 V
	Phase	1~
	Frequency	50 Hz
	Wire sizes	MUST comply with applicable legislation
Interconnection cabl (indoor↔outdoor)	e	4-core cable ≥1.5 mm² and applicable for 220~240 V
Recommended field	fuse	16 A
Earth leakage circuit	t breaker	MUST comply with applicable legislation

4.6.2 To connect the electrical wiring on the outdoor unit

- 1 Remove the service cover.
- 2 Open the wire clamp.
- 3 Connect the interconnection cable and power supply as follows:
 - a Interconnection cable
 - b Power supply cablec Circuit breaker

 - Earth leakage circuit breaker
 - Power supply Earth
- 4 Tighten the terminal screws securely. We recommend using a Phillips screwdriver.

Finishing the outdoor unit 4.7 installation

To finish the outdoor unit installation 4.7.1

Insulate and fix the refrigerant piping and interconnection cable




- Gas pipe Gas pipe insulation Interconnection cable
- Liquid pipe
- Liquid pipe insulation Finishing tape
- 2 Install the service cover.

To close the outdoor unit



NOTICE

When closing the outdoor unit cover, make sure that the tightening torque does NOT exceed 1.3 N·m.



Commissioning 5



NOTICE

NEVER operate the unit without thermistors and/or pressure sensors/switches. Burning of the compressor might result.

5.1 **Checklist before commissioning**

After the installation of the unit, first check the following items. Once all below checks are fulfilled, the unit MUST be closed, ONLY then can the unit be powered up.

The indoor unit is properly mounted.	
The outdoor unit is properly mounted.	
The system is properly earthed and the earth terminals are tightened.	
The power supply voltage matches the voltage on the identification label of the unit.	
There are NO loose connections or damaged electrical components in the switch box.	
There are NO damaged components or squeezed pipes on the inside of the indoor and outdoor units.	
There are NO refrigerant leaks.	
The refrigerant pipes (gas and liquid) are thermally insulated.	
The correct pipe size is installed and the pipes are properly insulated.	
The stop valves (gas and liquid) on the outdoor unit are fully open.	
The following field wiring has been carried out according to this document and the applicable legislation between the outdoor unit and the indoor unit.	
Drainage	
Make sure drainage flows smoothly.	
Possible consequence: Condensate water might drip.	
The indoor unit receives the signals of the user interface .	
The specified wires are used for the interconnection cable.	
The fuses , circuit breakers , or locally installed protection devices are installed according to this document, and have NOT been bypassed.	

Checklist during commissioning 5.2

To perform an air purge .

6 Disposal



To perform a test run.

5.3 To perform a test run

Prerequisite: Power supply MUST be in the specified range.

Prerequisite: Test run may be performed in cooling or heating

Prerequisite: Test run should be performed in accordance with the operation manual of the indoor unit to make sure that all functions and parts are working properly.

- 1 In cooling mode, select the lowest programmable temperature. In heating mode, select the highest programmable temperature. Test run can be disabled if necessary.
- 2 When the test run is finished, set the temperature to a normal level. In cooling mode: 26~28°C, in heating mode: 20~24°C.
- 3 The system stops operating 3 minutes after the unit is turned OFF.



INFORMATION

- Even if the unit is turned OFF, it consumes electricity.
- When the power turns back on after a power break, the previously selected mode will be resumed.

5.4 Starting up the outdoor unit

See the indoor unit installation manual for configuration and commissioning of the system.

6 Disposal



NOTICE

Do NOT try to dismantle the system yourself: dismantling of the system, treatment of the refrigerant, oil and other parts MUST comply with applicable legislation. Units MUST be treated at a specialised treatment facility for reuse, recycling and recovery.

6.1 Overview: Disposal

Typical workflow

Disposing of the system typically consists of the following stages:

- 1 Pumping down the system.
- 2 Bringing the system to a specialized treatment facility.



INFORMATION

For more details, see the service manual.

6.2 To pump down



DANGER: RISK OF EXPLOSION

Pump down - Refrigerant leakage. If you want to pump down the system, and there is a leak in the refrigerant circuit:

- Do NOT use the unit's automatic pump down function, with which you can collect all refrigerant from the system into the outdoor unit. Possible consequence: Self-combustion and explosion of the compressor because of air going into the operating compressor.
- Use a separate recovery system so that the unit's compressor does NOT have to operate.




NOTICE

During pump down operation, stop the compressor before removing the refrigerant piping. If the compressor is still running and the stop valve is open during pump down, air will be sucked into the system. Compressor breakdown or damage to the system can result due to abnormal pressure in the refrigerant cycle.

Pump down operation will extract all refrigerant from the system into the outdoor unit.

- Remove the valve cap from the liquid stop valve and the gas stop valve.
- 2 Carry out forced cooling. See "6.3 To start and stop forced cooling" on page 10.
- 3 After 5 to 10 minutes (after only 1 or 2 minutes in case of very low ambient temperatures (<-10°C)), close the liquid stop valve with a hexagonal wrench.
- 4 Check on the manifold if the vacuum is reached.
- **5** After 2-3 minutes, close the gas stop valve and stop forced cooling.



- a Gas stop valve
- Closing direction
- Hexagonal wrench
- d Valve cape Liquid stop valve

6.3 To start and stop forced cooling

There are 2 methods to perform forced cooling.

- Method 1. Using the indoor unit ON/OFF switch (if present on the indoor unit).
- Method 2. Using the indoor unit user interface.

6.3.1 To start/stop forced cooling using the indoor unit ON/OFF switch

1 Press the ON/OFF switch for at least 5 seconds.

Result: Operation will start.



INFORMATION

Forced cooling stops automatically after 15 minutes.

2 To stop operation sooner, press the ON/OFF switch.

6.3.2 To start/stop forced cooling using the indoor unit user interface


1 Set the operation mode to cooling.

For the procedure, refer to "To perform a test run" in the installation manual of the indoor unit.

7 Technical data

A **subset** of the latest technical data is available on the regional Daikin website (publicly accessible). The **full set** of latest technical data is available on the Daikin Business Portal (authentication required).

7.1 Wiring diagram



DAIKIN

ERE



DAIKIN ISITMA VE SOĞUTMA SİSTEMLERİ SAN.TİC. A.Ş. Küçükbakkalköy Mah. Kayışdağı Cad. No: 1 Kat: 21-22 34750 Ataşehir İSTANBUL / TÜRKİYE
Tel: 0216 453 27 00 Faks: 0216 671 06 00 Çağrı Merkezi: 444 999 0

DAIKIN EUROPE N.V.

Zandvoordestraat 300, B-8400 Oostende, Belgium

Copyright 2018 Daikin

3P519299-5B 2018.12